

| | | | | | | | | | | | | | | |
|------------|-------------------------|-------------|------------|-----------------|---------------|----------------------|------------|------------|------------|-----------|-------------|--------|----------------|-----------------------|
| 1 | 厂房工程 | 44658256.84 | 5965474.22 | 19011625.71 | 2923304.05 | 7106961.29 | 1780307.32 | 1777546.23 | 1554756.58 | 569737.09 | 3687379.00 | | | |
| | | 100.00% | 13.36% | 42.57% | 6.55% | 15.91% | 3.99% | 3.98% | 3.48% | 1.28% | 8.26% | | | |
| 1.1 | 桩基础工程 | 6192043.29 | 291399.30 | 4508275.60 | 424713.55 | 0.00 | 126983.03 | 143159.73 | 136061.44 | 50127.90 | 511269.63 | | | |
| | | 13.87% | 4.71% | 72.81% | 6.86% | 0.00% | 2.05% | 2.31% | 2.20% | 0.81% | 8.26% | | | |
| 1.2 | 建筑工程 | 18402008.88 | 2313054.42 | 10961114.64 | 1382971.60 | 0.00 | 672457.55 | 739114.31 | 594821.26 | 219129.34 | 1519431.93 | | | |
| | | 41.21% | 12.57% | 59.56% | 7.52% | 0.00% | 3.65% | 4.02% | 3.23% | 1.19% | 8.26% | | | |
| 1.3 | 钢结构工程 | 19301494.05 | 3278223.57 | 3530850.58 | 1103478.69 | 6881981.50 | 955981.66 | 876277.42 | 789914.87 | 290986.14 | 1593701.34 | | | |
| | | 26.52% | 16.98% | 18.29% | 5.72% | 35.66% | 4.95% | 4.54% | 4.09% | 1.51% | 8.26% | | | |
| 1.4 | 排水防雷工程 | 762710.63 | 82796.93 | 11384.89 | 12140.21 | 224979.79 | 24885.08 | 18994.77 | 33959.01 | 9493.71 | 62976.11 | | | |
| | | 62.88% | 10.86% | 1.49% | 1.59% | 29.50% | 3.26% | 2.49% | 4.45% | 1.24% | 8.26% | | | |
| 主要工料 指标 | 工料名称 | 人工(元) | 型钢(t) | 预应力混凝土管 桩(m) | 商品混凝土 (m3) | 彩钢板(m ²) | 钢筋(t) | 砖(千块) | 螺纹钢(t) | 钢支撑(kg) | 钢焊条 (kg) | 螺栓(kg) | 镀锌低碳钢 丝(kg) | 钢结构薄型 防火涂料 (kg) |
| | 每100m ² 工料指标 | 62393.83 | 214.39 | 258.28 | 110.13 | 64.83 | 9.58 | 6.20 | 9.58 | 107.20 | 153.96 | 119.58 | 94.71 | 1355.90 |